Ok Birim Tailings Storage Facility Project

Environmental and Social Impact Assessment

Volume B — Main Report

TETRA TECH COFFEY

OK TEDI MINING

GUIDE TO THE ENVIRONMENTAL AND SOCIAL IMPACT ASSESSMENT

The environmental and social impact assessment is presented in four volumes.

VOLUME A: EXECUTIVE SUMMARY

Volume A is an executive summary of the environmental and social impact assessment.

VOLUME B: MAIN REPORT

A stand-alone document that presents the findings of technical studies, including potential environmental (biophysical), social and cultural heritage impacts of the project, the management measures to be implemented and residual impacts and benefits.

The main report includes:

- Details of the purpose and viability of the project.
- Details on policies and legal frameworks of the project.
- Details on stakeholder engagement for the project.
- Descriptions of the proposed development and the alternatives considered.
- A description of the existing biophysical and social environment.
- Assessments of the project's impacts on the biophysical and social environment, including cumulative impacts.
- Proposed mitigation measures and the management framework for managing the project's impacts.

VOLUME C: ATTACHMENTS

The attachments are reports that inform the ESIA and include a cross-reference of this ESIA against the DEC guidelines and the EIR, the construction environmental and social management plan, and a conceptual TSF closure and rehabilitation plan

VOLUME D: APPENDICES

Technical reports generated to characterise the existing environmental, social and cultural heritage values, and where relevant, assist with identifying the potential impacts of the project.

The appendices are divided in four parts:

- Part 1 – Appendices A to C
- Part 2 – Appendices D to F
- Part 3 – Appendices G to J
- Part 4 – Appendices K to M

OK BIRIM TAILINGS STORAGE FACILITY PROJECT

Environmental and Social Impact Assessment – Volume B Main Report

Report reference number: 754-POMEN374244C_R08
22 June 2026

PREPARED FOR

Ok Tedi Mining Ltd (OTML)
1 Dakon Road, Tabubil,
Western Province, 332
Papua New Guinea

PREPARED BY

Tetra Tech Coffey PNG Limited
Level 2, Comrade Haus,
Comrade Place (off Frangipani Street), Hohola
National Capital District, Papua New Guinea
p: +675 7190 4043

PNGBN 1-64126

QUALITY INFORMATION

Revision history

Revision	Description	Date	Author	Reviewer	Approver
Rev0	Draft	2206/2026	Tetra Tech Coffey	DM	DM

Distribution

Report Status	No. of copies	Format	Distributed to	Date
Rev0	1	Word	OTML, CEPA	22/06/2026

Restriction on Disclosure and Use of Data

This document has been prepared by Tetra Tech Coffey PNG Limited on behalf of Ok Tedi Mining Ltd for the Ok Birim Tailings Storage Facility Project, for the purposes of preparing this environmental and social impact assessment. It is not intended to be used for, and should not be relied on, for any other purpose. Tetra Tech Coffey PNG Limited accepts no liability or responsibility whatsoever for, or in respect of, any use of, or reliance upon, this document by any third party. This document is based on the information available, and the assumptions made, as at the date of the document. This document is to be read in full. No excerpts are to be taken as representative of the findings without appropriate context. Unauthorised use of this document in any form is prohibited.

Copyright notice

Tetra Tech Coffey PNG Limited 2026
The contents of this document are protected by copyright. Copyright in this material is owned by Tetra Tech Coffey or various other rights holders. You may not copy or exercise any other rights in the material except for the purpose of viewing or printing for your non-commercial use.

CONTENTS

1. Introduction 1-1
1.1 Project overview 1-1
1.2 The Ok Tedi Mine operation 1-4
1.3 Project context 1-4
1.4 Project proponent 1-5
1.5 Statutory context 1-5
1.6 ESIA approach 1-5
1.7 ESIA scope and objectives 1-6
1.8 Structure of this ESIA 1-6
2. Purpose and viability of proposed development 2-1
2.1 Purpose of the development 2-1
2.1.1 Project objectives and benefits 2-1
2.1.2 Alignment with national frameworks 2-1
2.2 Viability of the project 2-4
2.2.1 Proponent's credentials 2-4
2.2.2 Capital costs 2-4
2.2.3 Scoping and feasibility studies 2-5
2.2.4 Environmental and social studies 2-7
3. Policy, legal and administrative framework 3-1
3.1 Relevant legislative framework and project permitting 3-1
3.1.1 *Mining (Ok Tedi Agreement) Act 1976* 3-1
3.1.2 *Ok Tedi Environment Management Act 2019* 3-3
3.1.3 Key regulatory and institutional roles 3-8
3.2 Other legislation and regulations 3-8
3.3 International environmental agreements 3-10
3.4 Relevant international standards, guidelines and corporate policies 3-11
3.4.1 International standards and guidelines 3-11
3.4.2 Corporate policies and standards 3-12
3.5 Standards and guidelines adopted for the project 3-12
3.5.1 Air quality 3-12
3.5.2 Noise and vibration 3-13
3.5.3 Surface water and freshwater aquatic ecology 3-13
3.5.4 Terrestrial ecology 3-14

3.5.5 Socio-economic 3-14
3.5.6 Mine closure 3-14
3.5.7 Natural hazards and major incidents 3-14
3.5.8 Other key standards 3-15
4. For the environmental and social impact assessment 4-1
4.1 General approach 4-1
4.1.1 Data sources 4-1
4.1.2 Key assumptions and limitations 4-2
4.2 Scope of technical studies 4-3
4.2.1 Data collection 4-3
4.2.2 Area of influence and study areas 4-3
4.3 Characterisation of existing environment 4-4
4.4 Impact assessment 4-4
4.4.1 Environmental impact assessment 4-5
4.4.2 Social impact assessment 4-6
4.4.3 Cumulative impact assessment 4-6
4.5 Application of mitigation hierarchy 4-7
5. Stakeholder engagement 5-1
5.1 Approach to engagement 5-1
5.1.1 OTML's current engagement approach 5-1
5.1.2 Engagement objectives for the project 5-1
5.1.3 Principles of engagement 5-2
5.2 Engagement process and activities 5-2
5.2.1 Project initiation and awareness 5-3
5.2.2 Information gathering and impact assessment 5-3
5.2.3 Pre-EIS submission disclosure 5-5
5.2.4 EIS disclosure 5-6
5.3 Stakeholder engagement requirements 5-6
5.3.1 PNG legislation 5-6
5.3.2 International standards 5-6
5.3.3 OTML policies 5-12
5.4 Key stakeholders 5-12
5.5 Engagement outcomes 5-14
5.5.1 ESIA engagement 5-14
5.5.2 Summary of issues raised 5-15

5.5.3 Key outcomes 5-24
5.6 Future engagement activities 5-25
5.7 Grievance and complaints management 5-25
6. Description of the proposed development 6-1
6.1 Project location and existing operations 6-1
6.1.1 The Ok Tedi Mine 6-1
6.1.2 Related development 6-5
6.1.3 Project area and footprint 6-5
6.2 Project components 6-6
6.2.1 Tailings storage facility 6-11
6.2.2 Roads, bridges and tailings pipeline infrastructure 6-24
6.2.3 Ancillary infrastructure 6-37
6.2.4 Materials and equipment 6-45
6.2.5 Traffic 6-48
6.2.6 Workforce 6-51
6.3 Project development schedule 6-51
6.4 Description of proposed project activities 6-52
6.4.1 Detailed design phase 6-52
6.4.2 Construction phase 6-52
6.4.3 Operations phase 6-58
6.4.4 Decommissioning, closure and rehabilitation phase 6-62
7. Assessment of key project alternatives 7-1
7.1 Overview and general approach 7-1
7.2 Not proceeding with the project 7-1
7.3 Key alternatives for the management of tailings 7-2
7.3.1 Previous studies 7-2
7.3.2 Multi-criteria alternatives assessment 7-5
7.3.3 Disposal alternatives for tailings 7-10
7.3.4 Transportation alternatives for tailings 7-11
7.4 Key alternatives for associated infrastructure 7-12
7.4.1 Hydro-cyclone house 7-12
7.4.2 Infrastructure corridor 7-12
7.4.3 Power supply 7-13
7.4.4 Water supply 7-13

8. Description of existing biophysical environment 8-1
8.1 Climate 8-1
8.1.1 Regional context 8-1
8.1.2 Project area 8-1
8.1.3 Climate related natural hazards 8-6
8.2 Topography, geology and soils 8-8
8.2.1 Tectonic setting 8-8
8.2.2 Natural hazards 8-10
8.2.3 Landforms 8-11
8.2.4 Geology 8-12
8.2.5 Soils 8-16
8.3 Physical riverine environment 8-28
8.3.1 Study area and method 8-28
8.3.2 Hydrology, geomorphology and sediment processes 8-30
8.3.3 Riverine sediment quality 8-47
8.3.4 Surface water quality 8-54
8.4 Groundwater 8-63
8.4.1 Study area 8-63
8.4.2 Groundwater units and geological features 8-63
8.4.3 Groundwater recharge and discharge 8-65
8.4.4 Groundwater systems 8-67
8.4.5 Groundwater quality 8-69
8.4.6 Groundwater uses 8-70
8.4.7 Groundwater dependent ecosystems 8-71
8.5 Aquatic ecology 8-73
8.5.1 Study area 8-73
8.5.2 Aquatic habitats 8-75
8.5.3 Aquatic flora 8-77
8.5.4 Aquatic fauna 8-79
8.5.5 Aquatic resource use 8-90
8.5.6 Critical habitat 8-92
8.6 Terrestrial ecology 8-93
8.6.1 Study method 8-93
8.6.2 Vegetation communities and habitats 8-96
8.6.3 Terrestrial flora 8-99

8.6.4 Terrestrial fauna 8-103
8.6.5 Key findings for conservation significant species 8-111
8.6.6 Protected areas 8-117
8.6.7 Critical habitat assessment 8-118
8.7 Air quality 8-122
8.8 Greenhouse gas emissions 8-124
8.9 Noise 8-125
9. Description of social environment 9-1
9.1 Introduction 9-1
9.2 Social characterisation 9-1
9.2.1 Social characterisation method 9-1
9.2.2 Social study area 9-2
9.2.3 Regional context 9-8
9.2.4 Local context 9-8
9.2.5 Summary of sensitivity of social values 9-70
9.3 Ecosystem services 9-72
9.3.1 Ecosystem services characterisation method 9-72
9.3.2 Priority ecosystem services screening 9-73
9.3.3 TSF communities 9-74
9.3.4 Infrastructure corridor 9-78
9.4 Archaeology and cultural heritage 9-80
9.4.1 Heritage characterisation method 9-80
9.4.2 Existing environment 9-83
10. Environmental impact assessment 10-1
10.1 Methods for environmental impact assessment 10-1
10.1.1 Significance assessment 10-2
10.1.2 Compliance assessment 10-5
10.1.3 Benchmarking assessment 10-5
10.2 Soils, landform and stability 10-5
10.2.1 Approach to impact assessment 10-5
10.2.2 Potential impacts 10-8
10.2.3 Avoidance, management and mitigation measures 10-11
10.2.4 Residual impact assessment 10-14
10.3 Groundwater 10-22
10.3.1 Approach to impact assessment 10-22

10.3.2 Potential impacts 10-24
10.3.3 Avoidance, management and mitigation measures 10-27
10.3.4 Residual impact assessment 10-28
10.4 Physical riverine environment 10-43
10.4.1 Approach to impact assessment 10-43
10.4.2 Potential impacts and improvements 10-53
10.4.3 Avoidance, management and mitigation measures 10-58
10.4.4 Residual impact assessment 10-61
10.4.5 Water quality compliance assessment 10-80
10.4.6 Watercourse residual impact and improvement zones 10-85
10.5 Aquatic biodiversity and ecology 10-88
10.5.1 Approach to impact assessment 10-88
10.5.2 Potential impacts 10-92
10.5.3 Avoidance, management and mitigation measures 10-95
10.5.4 Residual impact assessment 10-98
10.6 Terrestrial biodiversity and ecology 10-107
10.6.1 Approach to impact assessment 10-107
10.6.2 Potential impacts 10-110
10.6.3 Avoidance, management and mitigation measures 10-114
10.6.4 Residual impact assessment 10-118
10.6.5 Star Mountains Key Biodiversity Area 10-127
10.6.6 Biodiversity offset 10-127
10.7 Air quality 10-128
10.7.1 Approach to impact assessment 10-128
10.7.2 Potential impacts 10-130
10.7.3 Avoidance, management and mitigation measures 10-132
10.7.4 Residual impact assessment 10-132
10.8 Greenhouse gas emissions 10-139
10.8.1 Approach to assessment 10-139
10.8.2 Potential sources of GHG emissions 10-139
10.8.3 Avoidance, management and mitigation measures 10-140
10.8.4 Calculated GHG emissions 10-141
10.9 Noise and vibration 10-142
10.9.1 Approach to assessment 10-142
10.9.2 Potential impacts 10-143

10.9.3 Avoidance, management and mitigation measures 10-145
10.9.4 Modelled noise and vibration 10-146
11. Social, cultural, ecosystem services and human rights impact assessment 11-1
11.1 Social impact assessment 11-1
11.1.1 Assessment method 11-1
11.1.2 Drivers of potential social change 11-4
11.1.3 Impact assessment 11-6
11.1.4 Summary of key measures 11-61
11.2 Archaeology and cultural heritage impact assessment 11-65
11.2.1 Assessment method 11-65
11.2.2 Impact assessment 11-65
11.2.3 Cultural heritage management and mitigation 11-70
11.2.4 Residual impact assessment 11-72
11.3 Ecosystem services impact assessment 11-74
11.3.1 Assessment method 11-74
11.3.2 Ecosystems services impact assessment 11-74
11.4 Human rights impact assessment 11-81
11.4.1 Assessment method 11-81
11.4.2 Potential human rights impacts 11-89
12. Cumulative impact assessment 12-1
12.1 Important environmental and social aspects 12-1
12.2 Method for identifying credible projects 12-2
12.2.1 Credible projects 12-2
12.2.2 Spatial relationship 12-3
12.2.3 Temporal relationship 12-3
12.3 Identification of credible projects 12-3
12.4 Cumulative impact assessment 12-7
12.4.1 Physical disturbance - vegetation clearance 12-7
12.4.2 Physical disturbance - sedimentation 12-8
12.4.3 Physical disturbance – cultural heritage 12-9
12.4.4 Transport - road use 12-10
12.4.5 Transport – river and port use 12-11
12.4.6 Construction workforce – in-migration and access 12-12
12.5 Summary of cumulative impacts 12-13

13. Natural hazards, climate change and unplanned events 13-1
13.1 Regulatory and corporate frameworks 13-1
13.1.1 Applicable PNG legislation 13-1
13.1.2 Relevant OTML policies and standards 13-2
13.1.3 Applicable guidelines 13-4
13.2 Climate change risks 13-4
13.2.1 Assessment approach 13-5
13.2.2 Historical climate change 13-6
13.2.3 Future climate projections 13-7
13.2.4 Assessment of selected climate hazards 13-7
13.2.5 Risk management and assessment summary 13-12
13.3 Major accidents and unplanned events 13-13
13.3.1 Natural disasters 13-14
13.3.2 TSF failure or breach 13-16
13.3.3 Hazardous materials spill or leakage 13-27
13.3.4 Fire or explosion 13-29
13.3.5 Traffic accident (road, air or water) 13-30
13.3.6 Plant or mobile machinery accident 13-32
13.3.7 Epidemic or infectious disease outbreak 13-33
13.3.8 Civil unrest, protest or riot 13-34
13.4 Project emergency preparedness and response 13-35
13.5 Conclusion 13-36
14. Environmental and social management, monitoring and reporting 14-1
14.1 Environment management plan 14-1
14.2 Integrated management system 14-1
14.3 Environmental components of the IMS 14-5
14.3.1 Environmental standards 14-5
14.3.2 Environmental plans 14-8
14.4 Social components of the IMS 14-10
14.4.1 Description of social standards 14-10
14.4.2 Social plans 14-11
14.5 Risk management framework 14-11
14.6 Reporting 14-12
14.6.1 Incident and non compliance reporting and investigation 14-12
14.6.2 Quarterly reporting 14-12

14.6.3 Annual environmental report 14-12
14.6.4 Annual review 14-14
14.7 Project application 14-14
14.7.1 Management 14-14
14.7.2 Monitoring 14-14
15. Conclusion 15-1
16. Study team 16-1
16.1 Ok Tedi Mining Limited 16-1
16.2 Lead environmental and social consultant 16-1
16.3 Technical specialists 16-2
17. Acknowledgements 17-1
18. References 18-1
19. Glossary and abbreviations 19-1

LIST OF TABLES

Table 1.1 Structure of this environmental and social impact assessment 1-7
Table 2.1 Summary of pre-feasibility and related studies 2-5
Table 3.1 *Mining (Ok Tedi Agreement) Act 1976* supplemental agreements overview 3-2
Table 3.2 Status of OTML leases 3-3
Table 3.3 Summary of key statutory submissions 3-8
Table 3.4 Other environmental legislation and regulations 3-9
Table 3.5 International environmental agreements to which PNG is a signatory 3-10
Table 3.6 Relevant international standards and guidelines 3-11
Table 5.1 Copper Mark consultation requirements 5-7
Table 5.2 EP IV consultation requirements 5-8
Table 5.3 IFC PS consultation requirements 5-9
Table 5.4 GISTM consultation requirements 5-10
Table 5.5 Stakeholder groups 5-13
Table 5.6 Stakeholder engagement undertaken to date 5-14
Table 7.1 Ok Birim TSF location options 7-7
Table 7.2 Outcomes of the technology alternatives screening 7-9
Table 8.1 Relevant hydrometeorology stations for the Ok Tedi Catchment 8-3
Table 8.2 Climate parameters for the project area from PMP59 (1994 2024) and Bige stations (2019-2023) 8-4
Table 8.3 Summary of maximum soil survey results 8-22
Table 8.4 Assessment of potential acid sulfate soils along the infrastructure development corridor . 8-23
Table 8.5 Estimated thicknesses and sedimentation rates of mine sediment in the Fly River system 8-45
Table 8.6 Particulate copper content of Lower Ok Tedi area and Middle and Lower Fly levees (2023-2024) 8-49
Table 8.7 Riverine sediment quality table for infrastructure corridor watercourses 8-50
Table 8.8 Riverine sediment quality table for TSF development area watercourses 8-51
Table 8.9 Sulfur content of Lower Ok Tedi area and Middle and Lower Fly levees (2023 2024) 8-52
Table 8.10 ANC of Lower Ok Tedi area and Middle and Lower Fly levees (2023 2024) 8-54
Table 8.11 Surface water quality in the infrastructure development corridor watercourses 8-56
Table 8.12 Surface water quality in the TSF development area watercourses 8-57
Table 8.13 Freshwater macroinvertebrate taxonomy at Ok Birim 8-79
Table 8.14 Freshwater fish taxonomy in the TSF development area 8-80
Table 8.15 Freshwater fish taxonomy in the main Ok Birim channels (OB1 – OB4) 8-81

Table 8.16 Freshwater fish taxonomy in the Ok Ma study area 8-82
Table 8.17 WHO JECFA guideline values for metal concentrations in fish 8-83
Table 8.18 Terrestrial ecology survey methods 8-94
Table 8.19 Vegetation communities in the TSF development area 8-96
Table 8.20 IUCN listed flora species recorded in the terrestrial biodiversity study area 8-112
Table 8.21 Threatened or Protected fauna recorded or likely to occur in the terrestrial ecology study area 8-115
Table 8.22 Subspecies and taxa potentially new to science or undescribed recorded in the terrestrial ecology study area 8-116
Table 8.23 Subspecies and taxa with uncertain taxonomy recorded in the terrestrial ecology study area 8-117
Table 8.24 Quantitative thresholds for critical habitat criteria 1 to 4 8-118
Table 9.1 Demographic profile, TSF communities 9-16
Table 9.2 Highest level of educational attainment 9-36
Table 9.3 Reported water quality issues 9-43
Table 9.4 Food insecurity in TSF communities 9-46
Table 9.5 Infrastructure corridor population and housing, 2023 9-52
Table 9.6 Population estimates – construction haulage route 9-59
Table 9.7 Summary of services in regional centres 9-68
Table 9.8 Sensitivity of social values 9-70
Table 9.9 Priority ecosystem services screening 9-73
Table 9.10 Summary of community feedback from FGDs 9-76
Table 9.11 Summary of community feedback from infrastructure corridor villages 9-78
Table 9.12 Summary of cultural heritage sites – TSF development area 9-85
Table 9.13 Cultural heritage sites – TSF development area 9-86
Table 9.14 Field verified cultural heritage sites – TSF development area 9-88
Table 9.15 Archaeological finds 9-92
Table 9.16 Cultural heritage sites – infrastructure corridor 9-92
Table 10.41 Potential impacts to terrestrial biodiversity and ecological values according to project phases 10-110
Table 10.42 Proposed terrestrial biodiversity management measures 10-114
Table 10.43 Habitat hectare losses 10-119
Table 10.44 Habitat hectare gains 10-119
Table 10.45 Residual impact assessment: habitats 10-120
Table 10.46 Residual impact assessment: species 10-124
Table 10.47 Adopted project ambient air quality assessment goals 10-130

Table 10.1 General sensitivity criteria for environmental values 11-3
Table 10.2 General criteria for magnitude of impact..... 11-4
Table 10.3 Significance assessment matrix 11-4
Table 10.4 Definitions for the sensitivity of soil and landform environmental values 11-6
Table 10.5 Sensitivity of identified landforms and soil environmental values..... 11-7
Table 10.6 Potential impacts on identified soils and landform values according to project phases..... 11-8
Table 10.7 Proposed soils and land management measures 11-12
Table 10.8 Residual impact assessment – construction..... 11-19
Table 10.9 Residual impact assessment – operations 11-21
Table 10.10 Definitions for sensitivity of groundwater values..... 11-23
Table 10.11 Sensitivity of groundwater values 11-24
Table 10.12 Potential impacts to groundwater values according to project phases..... 11-25
Table 10.13 Proposed groundwater management measures 11-27
Table 10.14 Residual impact assessment for construction 11-29
Table 10.15 Residual impact assessment for operations..... 11-39
Table 10.16 Sensitivity rating of physical riverine environment aspects 11-45
Table 10.17 Specific criteria for magnitude of physical riverine impact or improvement..... 11-46
Table 10.18 Significance matrix of residual physical riverine impacts..... 11-47
Table 10.19 Significance matrix of residual physical riverine improvements 11-47
Table 10.20 Relevant surface water quality guidelines 11-48
Table 10.21 Upper river sediment transport modelled scenarios 11-50
Table 10.22 Potential impacts to the physical riverine environment according to project phases 11-53
Table 10.23 Potential improvements to the physical riverine environment according to project phases11-55
Table 10.24 Proposed management measures for the physical riverine environment 11-59
Table 10.25 Residual impact assessment construction phase..... 11-65
Table 10.26 Modelled cumulative deposition by reach from 1990 to 2060 for the scenario with TSF (Plan C) and without TSF (Plan D, shown in brackets) 11-67
Table 10.27 Residual impact assessment operational phase 11-79
Table 10.28 Background and predicted key water quality parameters upstream and downstream of the TSF 11-82
Table 10.29 Significance definitions for residual watercourse impacts and improvements 11-85
Table 10.30 Definition for the sensitivity of aquatic ecosystem health and aquatic fauna health..... 11-91
Table 10.31 Sensitivity of aquatic ecology values 11-91
Table 10.32 Potential impacts to aquatic biodiversity and ecological values according to project phases..... 11-93
Table 10.33 Proposed aquatic biodiversity management measures..... 11-96

Table 10.34 Residual impact assessment – construction 11-101
Table 10.35 Residual impact assessment – operations 11-104
Table 10.36 Residual impact assessment – restricted range and threatened fish species 11-106
Table 10.37 Significance matrix 11-107
Table 10.38 Criteria for sensitivity of receptor 11-108
Table 10.39 Sensitivity ratings 11-108
Table 10.40 Potential impacts to terrestrial biodiversity and ecological values according to project phases 11-110
Table 10.41 Proposed terrestrial biodiversity management measures 11-114
Table 10.42 Habitat hectare losses 11-119
Table 10.43 Habitat hectare gains 11-119
Table 10.44 Residual impact assessment: habitats 11-120
Table 10.45 Residual impact assessment: species 11-124
Table 10.46 Adopted project ambient air quality assessment goals 11-130
Table 10.47 Potential impacts to air quality values according to project phases 11-130
Table 10.48 Proposed air quality management measures 11-132
Table 10.49 Construction emissions 11-133
Table 10.50 Predicted daily and annual concentrations of TSP, $PM_{2.5}$, PM_{10} and NOx during construction 11-133
Table 10.51 Qualitative assessment 11-135
Table 10.52 Dust generation during TSF operations 11-136
Table 10.53 Predicted maximum concentrations of emissions from TSF operations 11-136
Table 10.54 Proposed GHG management measures 11-140
Table 10.55 Summary of estimated project GHG emissions during construction and operations 11-141
Table 10.56 Assessment goals for noise 11-142
Table 10.57 Potential impacts to noise values according to project phases 11-145
Table 10.58 Proposed noise and vibration management measures 11-145
Table 10.59 Predicted noise levels – TSF starter bund construction 11-147
Table 10.60 Predicted noise levels – TSF access roads and fixed infrastructure construction 11-147
Table 10.61 Predicted noise levels – infrastructure development corridor construction 11-148
Table 10.62 Predicted noise levels – TSF operation 11-148
Table 11.1 Sensitivity and magnitude criteria 11-2
Table 11.2 Significance evaluation matrix 11-3
Table 11.3 Potential for project-induced in-migration 11-6
Table 11.4 Proposed management measures – cultural identity and traditions 11-9
Table 11.5 Proposed management measures – social cohesion 11-11

Table 11.6 Proposed management measures – community safety 11-14
Table 11.7 Proposed management measures – community conflict 11-17
Table 11.8 Proposed management measures – landscape and amenity 11-28
Table 11.9 Proposed management measures – natural resource use 11-38
Table 11.10 Proposed management measures – employment, income and expenditure 11-43
Table 11.11 Proposed management measures – health and education services 11-47
Table 11.12 Proposed management measures – access and connectivity 11-50
Table 11.13 Proposed management measures – community health 11-52
Table 11.14 Proposed management measures – food and water security 11-57
Table 11.15 Summary of proposed management measures for social impacts 11-61
Table 11.16 Heritage sensitivity framework 11-65
Table 11.17 Cultural heritage values and potential impact significance – TSF development area 11-66
Table 11.18 Cultural heritage values and potential impact significance – infrastructure corridor 11-68
Table 11.19 Archaeology and cultural heritage management measures 11-71
Table 11.20 Residual archaeology and cultural heritage impacts 11-73
Table 11.21 Management measures – ecosystem services impacts 11-75
Table 11.22 Ecosystems services summary of impacts – TSF communities 11-77
Table 11.23 Ecosystems services summary of impacts – infrastructure corridor 11-80
Table 11.24 Potentially impacted human rights and core international instruments and standards 11-83
Table 11.25 Identified rightsholders 11-85
Table 11.26 Evaluation matrix for salience of potential human rights impacts 11-86
Table 11.27 Severity description and criteria for HRIA 11-87
Table 11.28 Likelihood description for HRIA 11-88
Table 11.29 Definitions of project connection to an impact 11-88
Table 12.1 Evaluation of projects 12-5
Table 12.2 Comparison of vegetation clearance associated with credible projects 12-7
Table 12.3 Context of cumulative vegetation disturbance 12-8
Table 13.1 Estimated historical and future precipitation intensities (mm/hr) near the project area and a comparison with the values reported by KCB (2024) 13-10
Table 13.2 Summary of project physical climate risk profiles and adaptation and management measures 13-12
Table 13.3 Incremental population at risk and potential loss of life estimates 13-23
Table 13.4 Dam safety inspection levels and frequency for ‘high A’ dam failure consequence category 13-25
Table 14.1 IMS components and related OTML standards 14-2
Table 14.2 OTML environmental standards 14-5

Table 14.3 Summary of monitoring requirements for the project 14-15
Table 16.1 OTML project team 16-1
Table 16.2 Tetra Tech Coffey environmental and social impact assessment team 16-1
Table 16.3 Technical specialists 16-2
Table 19.1 Glossary 19-1
Table 19.2 Abbreviations and acronyms 19-9

LIST OF FIGURES

Figure 1.1 Project location 1-2
Figure 1.2 Project components 1-3
Figure 3.1 OTML leases 3-4
Figure 3.2 OTEMA major permit amendment process 3-6
Figure 5.1 Communities engaged with during ESIA process 5-4
Figure 6.1 Tailings storage facility – proposed location and layout 6-7
Figure 6.2 Infrastructure corridor – proposed route and layout overview 6-8
Figure 6.3 Proposed Ok Birim TSF conceptual staging plan 6-18
Figure 6.4 Typical cross-section of the ultimate embankment for the proposed TSF 6-22
Figure 6.5 Typical layout of hydraulic sand cell construction 6-25
Figure 6.6 Conceptual flow diagram of the proposed hydro-cyclone house configuration 6-26
Figure 6.7 Simplified process flow diagram of materials flow 6-27
Figure 6.8 Conceptual cross-section of major access road co-located with tailings delivery pipeline 6-29
Figure 6.9 Conceptual cross-section of minor access road 6-30
Figure 6.10 Conceptual cross-section of temporary construction road/track 6-31
Figure 6.11 Conceptual 3D visualisation of proposed bridge crossings 6-35
Figure 6.12 Potential water extraction locations for the project 6-38
Figure 6.13 Typical large diameter pipeline construction sequence 6-55
Figure 6.14 Typical pipeline corridor cross-section 6-56
Figure 6.15 TSF conceptual water balance during operations 6-60
Figure 7.1 Alternative TSF site options considered 7-4
Figure 7.2 Ok Birim TSF site options and associated infrastructure corridor route alternatives 7-8
Figure 8.1 Regional hydrometeorology monitoring stations in the Ok Tedi and Fly River catchments . 8-2
Figure 8.2 Seasonal wind roses from Bige weather station (from 1994 to 2013) 8-5
Figure 8.3 Simplified tectonic plate boundaries, earthquakes and volcanoes 8-9
Figure 8.4 Project area landforms 8-13
Figure 8.5 Project area geology 8-14

Figure 8.6 Project area soils 8-17
Figure 8.7 Land facet groups within and around the TSF development area 8-18
Figure 8.8 Soil sampling locations along the infrastructure development corridor 8-21
Figure 8.9 River system overview 8-29
Figure 8.10 Mine area creeks 8-31
Figure 8.11 Longitudinal profiles of the mine area creeks and Middle Ok Tedi 8-33
Figure 8.12 Ok Tedi system 8-35
Figure 8.13 TSS in the Middle Ok Tedi and Middle Fly River 8-38
Figure 8.14 Fly River system 8-42
Figure 8.15 Levee sediment geochemistry trends 8-48
Figure 8.16 Boreholes and key features in the TSF development area 8-66
Figure 8.17 Limestone and karst features 8-72
Figure 8.18 Location of aquatic ecology study area 8-74
Figure 8.19 Fish species and occurrences recorded in the aquatic ecology assessment 8-89
Figure 8.20 Terrestrial ecology survey sites 8-95
Figure 8.21 FIMS vegetation mapping 8-98
Figure 8.22 Area of analysis for critical habitat assessment 8-120
Figure 9.1 Social characterisation study area 9-3
Figure 9.2 TSF communities 9-4
Figure 9.3 Infrastructure corridor communities – Ok Tedi Mine to TSF 9-5
Figure 9.4 Construction haulage route communities – Tabubil to Alice Pit 9-6
Figure 9.5 Construction haulage route communities – Alice Pit to Kiunga 9-7
Figure 9.6 Household survey responses – community safety 9-19
Figure 9.7 Landcover classification – gardening land 9-24
Figure 9.8 Landcover classification – sago 9-25
Figure 9.9 Landcover classification – cash crops 9-27
Figure 9.10 Health services used by the TSF communities 9-34
Figure 9.11 Education facilities used by the TSF communities 9-37
Figure 9.12 Access and transport routes 9-40
Figure 9.13 Locations of market stalls 9-42
Figure 9.14 Water source mapping 9-44
Figure 9.15 River communities and regional centres 9-65
Figure 9.16 TSF cultural heritage survey sites 9-91
Figure 10.1 Groundwater elevation contour map: pre TSF and at end of operations (2049) 10-32
Figure 10.2 Predicted groundwater elevation post closure 10-33

Figure 10.3 Predicted surface expressions of seepage 10-34
Figure 10.4 Sulfate concentrations in groundwater at the end of operations (2049) 10-36
Figure 10.5 Sulfate concentrations post closure 10-37
Figure 10.6 Total dissolved solids post closure 10-38
Figure 10.7 Copper concentrations post closure 10-41
Figure 10.8Arsenic concentrations post closure 10-42
Figure 10.9 Observed and predicted particulate copper concentrations for sediment delivered to the floodplain reaches of the upper river system 10-71
Figure 10.10 Observed and predicted particulate copper concentrations in Lower Ok Tedi levee sediments and in Upper Middle Fly levee sediments 10-72
Figure 10.11 Project affected watercourses and sub catchment associated with the TSF 10-76
Figure 10.12 Location of surface water quality monitoring and sampling points for the project 10-83
Figure 10.13 Predicted impacts to watercourses as a result of the project during construction 10-86
Figure 10.14 Predicted impacts and improvements to watercourses as a result of the project during operations 10-87
Figure 10.15 Aquatic ecology survey sites in the TSF development area: potentially exposed and reference sites 10-89
Figure 10.16 Aquatic ecology survey sites along the infrastructure development corridor: potentially exposed and reference sites 10-90
Figure 10.17 Air quality, noise and vibration sensitive receptors 10-129
Figure 10.18 Average daily and annual TSP emissions during TSF construction 10-134
Figure 10.19 Average daily and annual TSP emissions during TSF operations 10-137
Figure 10.20 Average annual PM2.5 and PM10 emissions during TSF operations 10-138
Figure 11.1 Conceptual view of the TSF (Cell 1 & 2) – looking south from Kungembit 11-20
Figure 11.2 Conceptual view of the TSF (Cell 1 & 2) – looking east from Ambaga 11-21
Figure 11.3 Views from within Kungembit village 11-22
Figure 11.4 Views from within Ambaga village 11-23
Figure 11.5 Views from within Karandimok village 11-24
Figure 11.6 Views towards the TSF from the entrance to Birimkamba village (TSF Cells 1 & 2) 11-25
Figure 11.7 Community resource use in Birimkamba 11-32
Figure 11.8 Community resource use in Kungembit 11-33
Figure 11.9 Community resource use in Ambaga 11-34
Figure 11.10 Community resource use in Karandimok 11-35
Figure 12.1 Credible and potential projects 12-4
Figure 13.1 Climate projections for the Fly River catchment. 13-8
Figure 13.2 Dam breach scenario locations 13-17
Figure 13.3 Cell 1 eastern break maximum depth 13-19

Figure 13.4 Cell 1 eastern break minimum time of arrival 13-20
Figure 13.5 Cell 2 eastern break maximum depth 13-21
Figure 13.6 Cell 2 eastern break minimum time of arrival 13-22
Figure 14.1 Environment management plan and the integrated management system 14-7
Figure 14.2 OTML risk management process 14-13

LIST OF PLATES

Plate 6.1 View of the existing Ok Tedi Mine 6-2
Plate 6.2 View of the existing tailings processing plant adjacent to the mine 6-2
Plate 6.3 View of the existing Kiunga–Tabubil Highway at intersection with Alice Pit access road 6-2
Plate 6.4 View of the existing Kiunga Port 6-3
Plate 6.5 View of the Ok Kumiup, which flows into the Upper Ok Tedi via Harvey Creek 6-3
Plate 6.6 View of the existing Bige dredge and stockpile operations 6-3
Plate 6.7 View of the proposed TSF development area 6-4
Plate 6.8 View of existing dirt road to be upgraded as part of the approved ITCS Road project 6-4
Plate 6.9 View of Alice Pit and proposed Alice Bridge crossing as part of the ITCS Road project 6-4
Plate 6.10 Representative example of hydro-cyclone house with primary cyclone cluster 6-41
Plate 6.11 Representative example of siphon system used at a TSF 6-41
Plate 6.12 Representative example of siphon discharge outlet to the receiving environment 6-41
Plate 8.1 Ridgeline soil profile exposure through road cutting 8-26
Plate 8.2 Roadway crossing over a perennial tributary 8-26
Plate 8.3 Seasonal tributary 8-26
Plate 8.4 The Ok Tedi captured from the eastern bank within the area 8-27
Plate 8.5 Pooling water within the floodplain facet group 8-27
Plate 8.6 Marshland facet group 8-27
Plate 8.7 Sulphide Creek 8-36
Plate 8.8 Harvey Creek 8-36
Plate 8.9 Ok Mani 8-36
Plate 8.10 Upper Ok Tedi 8-40
Plate 8.11 Middle Ok Tedi 8-40
Plate 8.12 Lower Ok Tedi 8-40
Plate 8.13 Upper Fly River 8-46
Plate 8.14 Upper Middle Fly River 8-46
Plate 8.15 Lower Middle Fly River near Everill Junction 8-46
Plate 8.16 Aquatic ecology site OB16 in the Ok Yep catchment 8-76

Plate 8.17 Aquatic ecology site OB09B in the Ok Yep catchment 8-76
Plate 8.18 Aquatic ecology site OB1 in the Ok Birim main channel 8-76
Plate 8.19 Aquatic ecology site OM6 in the Ok Ma catchment 8-78
Plate 8.20 Aquatic ecology site OM4 in the Ok Ma main channel 8-78
Plate 8.21 Aquatic ecology site OM12 in the Ok Ma catchment 8-78
Plate 8.22 Fly River rainbowfish (*Melanotaenia sexlineata*) 8-84
Plate 8.23 Swamp gudgeon (*Oxyeleotris stagnicola*) 8-84
Plate 8.24 Paska's blue Eye (*Pseudomugil paskai*) 8-84
Plate 8.25 Kiunga blue eye (*Kiunga leucozona*) 8-85
Plate 8.26 Ok Tedi rainbowfish (*Melanotaenia oktediensis*) 8-85
Plate 8.27 Striped cheek gudgeon (*Bostrychus strigogenys*) 8-85
Plate 8.28 Vegetation on low ridges and undulating slopes at Site 1 8-100
Plate 8.29 Inundated forest floor in the riverine zone at Site 1 8-100
Plate 8.30 Riverine vegetation near Site 2 8-100
Plate 8.31 Vegetation along flooded riverine plain 8-100
Plate 8.32 Dense shrub layer and herbaceous community 8-101
Plate 8.33 Streamside (riverine) vegetation near Site 2 8-101
Plate 8.34 Vegetation adjacent to the ITCS Road 8-101
Plate 8.35 *Begonia* sp.1 found at Site 1, likely new to science 8-102
Plate 8.36 *Begonia* sp.2 found at Site 1, likely new to science 8-102
Plate 8.37 Juvenile *Dillenia* sp.1 found at Site 1, likely new to science 8-102
Plate 8.38 *Glochidion* sp.1 found at Site 1, likely new to science 8-102
Plate 8.39 *Decalobanthus peltatus* 8-105
Plate 8.40 *Piper aduncum* 8-105
Plate 8.41 *Doryrhina muscinus* 8-106
Plate 8.42 *Nyctimene albiventer* 8-106
Plate 8.43 *Uromys caudimaculatus* 8-106
Plate 8.44 *Talegalla fuscirostris* 8-109
Plate 8.45 *Trugon terrestris* 8-109
Plate 8.46 King Bird of Paradise (*Cicinnurus regius*) 8-109
Plate 8.47 *Hylophorbus* sp.1 8-113
Plate 8.48 *Emoia kordoana* 8-113
Plate 8.49 Ground Boa (*Candoia aspera*) 8-113
Plate 8.50 Female *Nososticta ovimacula* 8-114
Plate 8.51 *Idiocnemis* cf. *schorri* 8-114

Plate 8.52 *Metagrion* cf. *annehueberae* 8-114
Plate 9.1 Aerial view of Kungembit 9-11
Plate 9.2 Community meeting area, Kungembit 9-11
Plate 9.3 View of Birimkamba village 9-12
Plate 9.4 Birimkamba village community area 9-12
Plate 9.5 Karandimok village 9-12
Plate 9.6 Trade store, Ambaga village 9-14
Plate 9.7 Kungim village 9-14
Plate 9.8 Boat ramp, Kungim village 9-14
Plate 9.9 Putmambin village 9-15
Plate 9.10 Komokpin village 9-15
Plate 9.11 ITCS Road construction dust 9-22
Plate 9.12 ITCS Road construction vehicle 9-22
Plate 9.13 Garden area (with sago palm in background), Ambaga village 9-26
Plate 9.14 Small garden plot, Putmambin village 9-26
Plate 9.15 Banana plants, Putmambin village 9-26
Plate 9.16 Ok Birim, near Karandimok village 9-29
Plate 9.17 Creek, Karandimok village 9-29
Plate 9.18 Example of a permanent house, Birimkamba village 9-33
Plate 9.19 Example of a semi-permanent house 9-33
Plate 9.20 Example of a traditional house, Karandimok village 9-33
Plate 9.21 Komokpin Primary School 9-38
Plate 9.22 Kungim school 9-38
Plate 9.23 Bush track, Birimkamba village 9-41
Plate 9.24 Dinghies located on the bank of the Ok Kaman, Komokpin village 9-41
Plate 9.25 ITCS Road looking west, Birimkamba 9-41
Plate 9.26 Water source, Karandimok village 9-45
Plate 9.27 Water sourced from spring, Birimkamba village 9-45
Plate 9.28 Rainwater tanks, Birimkamba village 9-45
Plate 9.29 Aerial view of Seven Kona community 9-48
Plate 9.30 Seven Kona community 9-48
Plate 9.31 Housing, Ok Ma community 9-49
Plate 9.32 Recreation area, Ok Ma community 9-49
Plate 9.33 Kolebon village, looking northwest 9-51
Plate 9.34 Hall, Kolebon village 9-51

Plate 9.35 Aerial view of Ok Tedi Bridge 9-56
Plate 9.36 Ok Tedi Bridge 9-56
Plate 9.37 Old Ok Ma Road looking south, Ok Ma community 9-57
Plate 9.38 Old Ok Ma Road looking north, Ok Ma community 9-57
Plate 9.39 Kiunga-Tabubil Highway, Tapko 9-61
Plate 9.40 Kiunga-Tabubil Highway, Haidawogam 9-61
Plate 9.41 Trade stores, Kiunga-Tabubil Highway 9-61
Plate 9.42 Kiunga-Tabubil Highway, Alice Pit 9-62
Plate 9.43 Dust from heavy vehicle convoy, Alice Pit 9-62
Plate 9.44 Ningerum township 9-67
Plate 9.45 Kiunga-Tabubil Highway, Ningerum township 9-67
Plate 9.46 ASM activity near Ningerum 9-67
Plate 9.47 Tabubil primary and elementary school 9-69